

Saratoga Sod farm **BIG ROLLS**



The Product

Labor saving Big Rolls are available for large, open area projects. Rolls measure 4'x84' (336 square feet/roll; 3 rolls/1,000 square feet), with two 2-foot wide ribbons of netting on each roll for ease of handling. One Big Roll weighs approximately 1,000 pounds, depending on the soil type and moisture content.

Netting is applied to Big Rolls at time of harvest to provide a neat, tight roll that better withstands handling and roll out. We recommend that netting be removed during installation.



Potential sod stretch during handling and installation inhibits exact length cuts. Therefore, trimming may still be necessary.

Due to their size, sod in Big Rolls can not be graded out the same as small rolls. Therefore, it may be necessary to cut portions of the Big Rolls and pull back together.

Site Preparation

Your job site should be prepared essentially the same for a Big Roll project as for any small roll project. The major difference is that the ground must be very firm (but not compacted) so that equipment (tractor, forklift or track machine) can drive on it without leaving tracks.

To facilitate your project, we request that Big Roll orders be a minimum of 6,000 square feet. Big Rolls are ideal for large, wide-open areas that are level or have a gentle slope.



For smaller areas where it is difficult to maneuver machinery (short runs, obstacles, curbs, etc.) or on grades greater than a 10% slope, we recommend using standard palletized rolls (2'x5').

To facilitate unloading and sod placement, and to provide you with the most efficient service, it is essential that we are able to park and unload tractor trailers near the site. The sod staging area must be easily accessible. If the site is difficult to access, or if we have to transport sod over 25 yards from the unloading site, please let us know when you place your order.

We allow one hour per tractor trailer for unloading. If the site requires a longer unloading period, we will be happy to assist you for \$70 per hour. When possible, please let us know prior to delivery so we can plan accordingly.



Installation

Due to their size, Big Rolls can not be unrolled and installed by hand like standard palletized rolls.

When installing Big Rolls, you have 3 options:

1. Unroll and **install the sod yourself** using either a tractor (at least 40 Hp, preferable with turf tires), skid steer, or forklift and an unrolling attachment from Saratoga Sod.
2. **Saratoga Sod provides a roll-out service** with a man and machine to unroll the sod. You provide the labor (at least 5 people) to actually install the sod.
3. **Saratoga Sod provides a complete installation service.** We can assist with site preparation if needed. You are responsible for post-installation watering and care.



You are responsible for the following to properly install Big Rolls:

1. Labor (4-5 people works best) to pull the sod into place, fit, cut and trim the sod. Steel hand rakes work well to pull/push the sod, and sharp knives are needed to cut and trim the sod.
2. If an underground irrigation system is in place, clearly mark all heads with flags so they will not be run over with machinery. Make sure the system works properly prior to sod installation.
3. Have the area prepared and ready when sod is delivered to the site. **Sod must be unrolled and installed immediately upon delivery.**
4. **Water sod immediately and thoroughly following installation!** For large jobs, irrigate sections as they are completed. Do not wait until the end of the day to begin irrigating.

A tractor trailer contains 10,000 square feet of Big Roll sod (30 Big Rolls). Unloading time is approximately one hour per trailer. As long as all of the above conditions have been met, our operators can unroll 10,000 square feet of Big Rolls in approx. 2 hours.

Our operator will work with you to help in every way possible. However, if you are not properly prepared or do not have adequate labor to install with the rollout service, delays and prolonged time at the job site will incur additional charges of \$70 per hour.



Cost

Big Roll Sod

Please see current price list for pricing, based on total square footage. Add 1¢ per square foot for Big Rolls.

Rollout Service

Add 5-6¢ per square foot (man and machine from Saratoga Sod + your labor), depending on site and quantity.

Installation

Please call for further information and pricing regarding a complete installation service.

Tubes

\$15 refundable deposit per tube.

Attachments

A \$250 deposit is required for use of a roll-out attachment for either a 3 point hitch or forks. Please return the attachment and tubes the day following installation. Attachments that are not returned the next business day will be charged a non-refundable rental fee of \$50 per day.

If you have questions or need additional information, please contact us:

Saratoga Sod
1670 Route 4
Stillwater, NY 12170

518-664-5038
info@saratogasod.com
SaratogaSod.com